

Addendum #1, March 16, 2017 – Perimeter Activity Center – ITS Upgrades & System Expansion

In response to Bidder Questions / Inquiries:

1. Are there multiple ducts available where the fabric is intended to be pulled? How is it intended to pull the fiber and fabric in same duct where fiber is already installed?

Response: Multiple conduits are existing. Contractor will need to verify availability of conduits. Fabric is intended for easier install of fiber in existing conduits.

2. Do the CCTV's and mounting arms need to paint match the existing mast arms?

Response: No.

Notes from Pre-Bid Conference, March 2, 2017:

1. Upcoming Milestone Dates:

** Bids Due: 12:00 noon on March 23, 2017

** Bid Opening: 3:00 PM on 3/23/17

2. DBE Goal / Participation / Reporting: 16%
3. Refer to page 16 of the Bid Package for the items required for a responsive bid.
4. Submit itemized bid on the Schedule of Items bid form (page 44 of the bid package)
5. Attention drawn to the following specification sections:
 - a. Section 105 – Coordination between contractors
 - b. Section 108 – Prosecution & Progress
 - i. Liquidated Damages stipulated
 - ii. LDs will be strictly enforced
 - c. Section 107.25 (p. 158) – Disruption to Residential & Commercial Property
 - i. Leave disturbed areas equal to or better than the way you found it.
6. High level review of construction documents by Kimley-Horn
 - a. Contractor will be tying into existing GDOT fiber
 - b. Contractor to maintain connectivity with City of Sandy Springs
 - c. Some devices will be installed by City of Dunwoody
7. PCID comments:
 - a. Contractor will be required to coordinate permits with three (3) separate jurisdictions: City of Brookhaven, City of Dunwoody and City of Sandy Springs
 - b. Disruption of traffic:
 - i. Absolutely no lane closures / disruption of traffic during the Holidays (Thanksgiving thru New Years)
 - c. Document utilities
 - d. Coordination with concurrent projects:
 - i. Upcoming project at I-285/400 interchange – contractors need to work with PCID to navigate
 - ii. State Farm
 - e. Coordinate traffic control with PCID during switch-over.